

**St. Tammany Parish Communications District 9-1-1 Dispatch Center**

BID NO.: NF-2016-11-17

GLA Project No. 14109

**ADDENDUM NO. 2**

**BID NO.: NF-2016-11-17**  
**New 9-1-1 Communications Facility**

Date: 09 January 2017

The following clarifications, changes, additions or deletions for this project shall be made to the Contract Documents; all other conditions and work shall remain unchanged. The Addendum supersedes current conditions shown in the Contract Documents. **Acknowledge the receipt of these Addenda by inserting its number and date in your bid.** The following revisions to the Specifications and/or Drawings for the project shall become a part of the above numbered Contract Documents.

**1.0 General**

- 1.1 The Owner has completed clearing of the project site. A site survey, dated January 2017, was completed by Landmark Surveying, Inc. and is issued with this Addendum as both a pdf and a CAD file.

**2.0 Drawings:**

- 2.1 On sheet A 401, Detail 2: Revise keynote (9) that reads "Aluminum Composite Panel Wall Cladding (Accent Color)." This keynote should be the number (1). The ACM cladding is a consistent color (Field Color) along the entire west elevation.

**3.0 Substitution Requests**

The following Substitution Requests submitted to date are acceptable to the Architect PROVIDED the products meet all the project performance requirements in the Contract Documents, local codes, and AHJ review. Final review of all substitution requests approved for bidding herein will be conducted upon final submittals provided by the selected Contractor.

1. Staticworkx Carpet Tile. Upon project completion, the manufacturer or the manufacturer's approved representative shall test the resistive properties of the floor per the test method ANSI/ESD STM 7.1. The test results shall be confirmed in writing certifying that the flooring resistance properties meet Motorola R56 criteria.
2. TRANE for project controls in addition to listed vendors in Specification 23 09 00.



**St. Tammany Parish Communications District 9-1-1 Dispatch Center**  
BID NO.: NF-2016-11-17  
GLA Project No. 14109

**ADDENDUM NO. 2**

3. ACCUTRACK Systems Fabric Wrapped Panels.
4. Priority Systems, Inc. For Fire Alarm System: Siemens.
5. Superior Products: Champion Pumps SP-1 and SP-2.
6. Plumbing fixtures as submitted by Hamilton Sales, Inc. pending modifications required by engineer review.
7. Plumbing fixtures as submitted by BBWC pending modifications required by engineer review.
8. Sump pumps as submitted by Gaudin Equipment.
9. Acorn wire & Iron Works for Wire Mesh Partitions.
10. Bell and McCoy lighting fixtures pending any modifications required by engineer review.
11. SWFcontract commercial window treatments: SL20 Roller Shades.

**END OF ADDENDUM NO. 2**

